

January 8, 2023

**PASCAGOULA PUBLIC LIBRARY  
REPAIRS AND RENOVATIONS  
JACKSON COUNTY BOARD OF SUPERVISORS  
PASCAGOULA, MISSISSIPPI**

**00.910 ADDENDUM NO 2.**

This Addendum contains 1 page and 0 pages of attachments for a total of 1 page.

The Bidder acknowledges that it is the Bidder's responsibility to ascertain whether any Addenda have been issued and if so, to obtain copies of such Addenda. Bidder therefore agrees to be bound by all Addenda that have been issued for this Bid.

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents. The following clarifications, changes, additions, or deletions shall be made to the following documents as indicated and all other conditions shall remain the same.

**CHANGES TO THE PROJECT MANUAL**

- A. 07.521 Styrene-Butadiene-Styrene (SBS) Modified Bituminous Membrane Roofing
  - 1. Part 1.11 Performance Requirements
    - a. Change E. to read: "E. Cyclic Fatigue: 1. The roof system shall pass ASTM D5849 Standard Test Method for Evaluating Resistance of Modified Bituminous Roofing Membrane to Cyclic Fatigue (Joint Displacement). Passing results shall show no signs of cracking, splitting, or tearing over the joint."

**CHANGES TO THE DRAWINGS**

- 1. SHEET E203 – First Floor New Power, Fire Alarm, and Mechanical Systems Plan
  - A. AHU/2 shall have (2) duct mounted smoke detectors. One is supply and One in return ducts.
  - B. Add Specific Note #7 to read: "Coordinate with Mechanical for reconnection of wall louvers. 2-#12, 1-#12G in ½" c. Reconnect to existing circuit." This note is in reference to louvers located in Mechanical Room 108.
- 2. SHEET E204 – 2nd Floor New Power, Fire Alarm and Mechanical Systems Plan
  - A. AHU/4 shall have (2) duct mounted smoke detectors. One is supply and one in return ducts.

END OF ADDENDUM #2 (Plus 0 Pages of Attachments)